

ENERGY CONSERVATION PROJECT: **A/C** SAVINGS REPORT

SITE:LS MILLS LTD., THENI. UNIT:"B"

DATE: 30.01.12 - 10.02.12

S.NO	LOCATION	DATE	WITHOUT SAVER							DATE	WITH SAVER							% OF SAVINGS	REMARKS
			TIME			READING		CON.UNIT			TIME			READING		CON.UNIT			
			OPEN	END	HOURS	OPEN	END	TOTAL	AVE/ HRS		OPEN	END	HOURS	OPEN	END	TOTAL	AVE/ HRS		
1	SERVER(HC)R	31.01.12	3.44PM	9.44PM	6	38.6	52.5	13.9	2.32	30.01.12	3.44PM	9.44PM	6	5.7	16.5	10.8	1.80	22.30%	
2	SERVER(HC)R	01.02.12	3.44PM	9.44PM	6	94.9	106.6	11.7	1.95	02.02.12	3.44PM	9.44PM	6	148	157.7	9.7	1.62	17.09%	
3	SERVER(HC)L	04.02.12	10.05AM	5.05PM	8	56.4	74.0	17.6	2.20	03.02.12	10.5AM	5.05PM	8	5.0	20.1	15.1	1.89	14.20%	
4	SERVER(HC)R	07.02.12	9.40AM	5.40PM	8	320.8	344.0	23.2	2.90	06.02.12	9.00AM	5.00PM	8	270.3	288.2	17.9	2.24	22.84%	
5	SERVER(HC)R	07.02.12	9.40AM	5.40PM	8	320.8	344.0	23.2	2.90	08.02.12	9.25AM	5.25PM	8	385.7	403.5	17.8	2.23	23.28%	
6	G.M(OFFICE)	02.02.12	10.00AM	5.00PM	8	14.8	27.1	12.3	1.54	03.02.12	10.00AM	5.00PM	8	28.9	40.7	11.8	1.48	4.07%	
7	G.M(OFFICE)	08.02.12	9.35AM	5.35PM	8	72.2	92.5	20.3	2.54	07.02.12	9.35AM	5.35PM	8	54.8	70.0	15.2	1.90	25.12%	
8	MD ROOM	02.02.12	10.00AM	5.00PM	8	25.0	41.0	16.0	2.00	03.02.12	10.00AM	5.00PM	8	50.0	64.3	14.3	1.79	10.63%	
9	MD ROOM	08.02.12	9.35AM	5.35PM	8	114.8	136.2	21.4	2.68	07.02.12	9.35AM	5.35PM	8	90.0	107.7	17.7	2.21	17.29%	
10	QC ROOM	31.01.12	12.10PM	5.10PM	5	25.1	38.6	13.5	2.70	30.01.12	12.10AM	5.10PM	5	4.8	16.1	11.3	2.26	16.30%	
11	QC ROOM	04.02.12	10.15AM	5.15PM	8	102.5	120.5	18.0	2.25	03.02.12	10.15AM	5.15PM	8	83.3	98.7	15.4	1.93	14.44%	
12	QC ROOM	06.02.12	8.45AM	4.45PM	8	121.7	143.9	22.2	2.78	07.02.12	9.05AM	5.05PM	8	147.1	165.2	18.1	2.26	18.47%	
13	QC ROOM	08.02.12	8.45AM	4.45PM	8	167.0	189.4	22.4	2.80	07.02.12	9.05AM	5.05PM	8	147.1	165.2	18.1	2.26	19.20%	
13	STITCH MD	08.02.12	9.00AM	5.00PM	8	37.8	44.8	7.0	0.88	07.02.12	9.10AM	5.10PM	8	31.0	37.1	6.1	0.76	12.86%	
14	STUDIO	08.02.12	9.00AM	5.00PM	8	34.3	43.5	9.2	1.15	07.02.12	9.10AM	5.10PM	8	20.1	28.3	8.2	1.03	10.87%	
15	UPS 1	02.02.12	10.10AM	5.10PM	8	224.4	275.4	51.0	6.38	01.02.12	10.10AM	5.1PM	8	92.3	135.3	43	5.38	15.69%	
16	UPS 1	04.02.12	10.00AM	6.00PM	8	516.2	575.6	59.4	7.43	03.02.12	10.10AM	6.10PM	8	379.8	424.1	44.3	5.54	25.42%	
17	UPS 1	08.02.12	9.10AM	5.10PM	8	1107.0	1172.8	65.8	8.22	07.02.12	9.15AM	5.15PM	8	958.4	1014	55.8	6.98	15.20%	
18	UPS2	08.02.12	9.10AM	5.10PM	8	746.8	798.0	51.2	6.40	07.02.12	9.15AM	5.15PM	8	628.5	673.3	44.8	5.60	12.50%	
19	UPS1	08.09.02.12	9.10AM	9.10AM	24	1107	1284.1	177.1	7.38	06.07.02.12	10.15AM	10.15AM	24	819.9	964.6	144.7	6.03	18.29%	
20	UPS1	09.02.12	9.10AM	5.10PM	8	1284.1	1350.4	66.3	8.29	10.02.12	9.35AM	5.35PM	8	1467	1522	55.2	6.90	16.74%	
21	UP2	09.02.12	9.10AM	5.10PM	8	869.4	920.9	51.5	6.44	10.02.12	9.35AM	5.35PM	8	999.9	1046	45.6	5.70	11.46%	
22	QC ROOM	09.02.12	10.16AM	5.16PM	8	196.2	216.8	20.6	2.58	10.02.12	9.10AM	5.10PM	8	218.5	237.2	18.65	2.33	9.47%	4 Times Power Cut

* SERVER(HC)R -HIGH COOL RIGHT SIDE

*D.G.M(OFFICE) -TEMP *QC ROOM - TEMP 21C

* STUDIO-TEMP *CON.UNIT-CONSUMED UNIT

ENERGY CONSERVATION PROJECT: **A/C** SAVINGS REPORT

SITE:LS MILLS LTD., THENI. UNIT:"A"

DATE: 01.02.12 -10.02.12

S.NO	LOCATION	DATE	WITHOUT SAVER							DATE	WITH SAVER							% OF SAVINGS	REMARKS
			TIME			READING		CON.UNIT			TIME			READING		CON.UNIT			
			OPEN	END	HOURS	OPEN	END	TOTAL	AVE/ HRS		OPEN	END	HOURS	OPEN	END	TOTAL	AVE/ HRS		
2	DGM (P)	04-06.02.12	9.30AM	5.30PM	8	79.85	125.1	45.25	5.66	07-08.02.12	9.30AM	5.30PM	8	128.65	162.35	33.7	4.21	25.52%	
3	GUEST 2	07.02.12	11.45AM	5.45PM	8	10.45	21.0	10.6	1.75	03.02.12	11.40AM	5.40PM	8	3.4	8.35	4.95	0.83	53.08%	
4	GUEST 2	08.02.12	11.45AM	5.45PM	8	22.85	33.15	10.3	1.71	03.02.12	11.40AM	5.40PM	8	3.4	8.35	4.95	0.83	51.94%	
5	DRYER	10.02.12	12.05AM	3.05PM	3	323.8	339.5	15.7	5.23	10.02.12	6.05AM	9.05AM	3	300.5	311.1	10.6	3.53	32.48%	DC set Runing
6	DRYER																		
6	MARKETING																		
7	STORE																		
8	GUEST 1																		
9	MAIN OFF																		

*DGM (P) -TEMP 21C

* GUEST 1,2 -TEMP HIGH COOL

*CON.UNIT-CONSUMED UNIT